# BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/03/2016-17, Date:16.08.2016 ITEM NO: 09

SCHEDULE-B

NAME OF WORK: Improvements to roads & drains at 10th cross & other cross roads at Manjunatha nagara Ward No 14 Bagalagunte

| Sl. No | Description of work | Unit | Qty | Rates Quoted by Contractor M.R.Girish Gowda | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | In Words (Rs.) |
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. complete as per the direction of Engineer-in-charge of the work. | Cum | 252 | 83.16 | Rupees Eighty Three and Sixteen Paise Only |
| 2 | Removing B.S.Slab of drain and stacking etc., complete as per the direction of Engineer-in-charge of the work. | Sqm | 81 | 63.72 | Rupees Sixty Three and Seventy Two Paise Only |
| 3 | Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work. | Cum | 13.5 | 5070.6 | Rupees Five Thousand Seventy and Sixty Paise Only |
| 4 | Providing and laying in position plain cement concrete of mix 1:3:6 with OPC Cement @220 kgs with 20 mm and down size graded granite metal course aggregates @ 0.84 cum and fine aggregates @0.56 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well comated, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per the direction of Engineer-in-charge of the work. | Sqm | 6 | 5491.8 | Rupees Five Thousand Four Hundred Ninety One and Eighty Paise Only |

Signature of the Contractor

Executive Engineer

| | | | | | |
|---|---|---|---|---|---|
| 5 | Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work. | cum | 10.6 | 5490.72 | Rupees Five Thousand Four Hundred Ninety and Seventy Two Paise Only |
| 6 | Refixing stone slabs of drains and pointing in CM 1:3 etc complete as per the direction of Engineer-in-charge of the work. | Sqm | 121.5 | 78.84 | Rupees Seventy Eight and Eighty Four Paise Only |
| 7 | Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick complete as per the direction of Engineer-in-charge of the work. | Sqm | 81 | 663.12 | Rupees Six Hundred Sixty Three and Twelve Paise Only |
| 8 | Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work. | Sqm | 180 | 950.0 | Rupees Nine Hundred Fifty Only |
| 9 | Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. | Sqm | 373.5 | 1300.0 | Rupees One Thousand Three Hundred Only |
| 10 | For Grading I material construction of granular sub-base by providing coarse graded crushed stone aggregates of Granite/ trap/basalt material spreading in uniform layers with motir grader on prepared surface mixing by a mix in place method with rotawater at OMC, and Compacting with vibratory roller to achieve the desired density, complete as per specifications.by mix in a Place method for course Graded Granular Sub Base Material as per 400-2 for grading I material complete as per the direction of Engineer-in-charge of the work. | Cum | 75 | 1200.0 | Rupees One Thousand Two Hundred Only |

Signature of the Contractor

Executive Engineer

| | | | | | |
|---|---|---|---|---|---|
| 11 | Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. | Cum. | 150 | 1300.0 | Rupees One Thousand Three Hundred Only |
| 12 | Providing and applying primer coat with S.S. Bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. | Sqm | 750 | 32.4 | Rupees Thirty Two and Forty Paise Only |
| 13 | Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. complete as per the direction of Engineer-in-charge of the work. | Sqm | 2750 | 3.24 | Rupees Three and Twenty Four Paise Only |
| 14 | Providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all Materials, labour, HOM of machineries complete as per the direction of Engineer-in-charge of the work. | Sqm | 2750 | 15.12 | Rupees Fifteen and Twelve Paise Only |
| 15 | Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, 50/75mm compacted thickness with 3.3% bitumen but excluding the cost of primer/tack coat with lead incl. cost of all materials, labour, HOM of machineries complete as per specifications with 80/100 grade bitumen using 40/60TPH capacity H.M.P with Mechanical paver Gr II (50/75mm) with 3.3% VG-30 Bitumen as per the directions of Engineer-in-charge of the work | Cum | 37.5 | 5500.0 | Rupees Five Thousand Five Hundred Only |

Signature of the Contractor

Executive Engineer

| | | | | | |
|---|---|---|---|---|---|
| 16 | Providing and laying bituminous concrete with hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder and filter transporting the hot mix to work site laying with paver finisher to the required grade, level and alignment. rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORTH Speicification clause no 500.9 complete in all respects complete as per specification no 509. using 40/60 TPH Capacity H.M.P With Mechanical paver Gr-II (30 mm to 45 mm) with 6% VG-30 Bitumen complete as per the direction of Engineer-in-charge of the work. | Cum | 123.75 | 8400.0 | Rupees Eight Thousand Four Hundred Only |
| 17 | Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per the direction of Engineer-in-charge of the work. | Cum | 252 | 84.5 | Rupees Eighty Four and Fifty Paise Only |

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,